

RECEIVED  
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3  
Rev. 1-8-82

MAR 16 1982

CONSERVATION DIVISION  
Wichita, Kansas

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-069-20128-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Samuel Gary Oil Producer

Complete Address #4 Inverness Court East Longwood Colo 80112-5699

Lease Name Snowbarger Well No. 6-5

Location SW NW Sec. 6 Twp. 25 Rge. 28N (East)(West)

County Gray Total Depth 5020'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated This well was equipped but never produced.

Plugging Contractor Sargants Casing Pulling Service

Address 6205 Lincoln Box 506 Liberal Kansas 67901 License No. 511

Operation Completed: Hour: 11:30AM Day: 8 Month: March Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

There is 4963' of <sup>4 1/2"</sup> production pipe cemented out side pipe to 4063'.  
The perforations were from 4690' to 4742'. 1st plug cemented off  
bottom hole with 25 sbx of cement. 2nd plug at 897' with  
35 sbx of cement. 3rd plug at 40' to 0' with 10 sbx of cement.  
The cement was pumped down through production pipe.  
They recovered <sup>2 8 3/8"</sup> ~~2856'~~ <sup>4 1/2"</sup> of ~~4 1/2"~~ production pipe. The plugging  
was accomplished by Sargants Casing Pulling Service.

Amount of Surface Casing: 897' of 8 5/8" cement circulated.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthis  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was on another well that was more important.

Signed: Paul Luthis  
Conservation Division Agent

INVOICED

DATE 3-16-82

INV. NO. 9668-W