



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*Plugging Authority issued  
May 14, 1975*

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1975

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

CONSERVATION DIVISION  
Wichita, Kansas

05-19-75

Operator's Full Name Petroleum, Inc.  
 Complete Address P.O. Box 1255, Liberal, Kansas 67901  
 Lease Name Federal "C" Well No. 1  
 Location Opp. NW. SW. Sec. 18 Twp. 25 Rge. (E) (W) 34  
 County Turney Total Depth 5180  
 Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
 Other well as hereafter indicated \_\_\_\_\_  
 Plugging Contractor Sargent's Casing Pulling  
 Address Liberal, Kansas License No. 633  
 Operation Completed: Hour 5:00 PM Day 16 Month May Year 1975

The above well was plugged as follows:

*There was 847' of 8 1/8" surface casing  
5 1/2" casing set to 5180 ft. Casing collapsed  
at 4100'. set 1st plug set at 4100' with 20 sacks  
of cement displaced with 90 barrels of mud  
2nd plug set at 897' with 35 sacks of cement  
displaced with 17 barrels of Rotary Mud. 3rd  
plug set at 33' with 10 sacks of cement.  
There was 1360' of 5 1/2" casing salvaged.*

I hereby certify that the above well was plugged as herein stated.

Signed: Charles Thomas  
Well Plugging Supervisor

INVOICED

DATE 5/21/75

INV. NO. 1353-w