

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -047- 20,497-0000 (of this well)

Operator's Full Name Dean James

Complete Address 900 N. Tyler Rd., Suite 11, Wichita, Ks. 67212

Lease Name Julian Well No. 1

Location NE SE NE Sec. 23 Twp. 25S Rge. 16 (E) (W) X

County Edwards Total Depth 4400

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:45 Am. Day 7 Month 8 Year 1980

The above well was plugged as follows:

468' 8 5/8" casing w/223 sax cement. 4 1/2" casing set at 4360' w/100
sax cement. Top pref's at 4322'-34'-Sand back to 4300'-Top sand w/4
sax mixed cement w/dump bailer-Pull 3515' casing. Allied mixed &
pumped 8 sax hulls-25 sax gel-150 sax 50/50 posmix cement w/4% gel
& 3% cc in 8 5/8" casing back to zero feet. Shut in w/600# pressure.

RECEIVED 08-11-80
STATE CORPORATION COMMISSION

AUG 13 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8-12-80

INV. NO. 2838-W