

15-057-20041-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Ford County, Sec. 6 Twp. 26S Rge. (E) 21W (W)
C SW NW

Location as "NE/CNWxSWx" or footage from lines _____
Lease Owner Okmar Oil Company
Lease Name Torline Well No. 1
Office Address 1130 Vickers-KSB&T Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-27 1972
Application for plugging filed 10-27 1972
Application for plugging approved 10-27 1972
Plugging commenced 10-27 1972
Plugging completed 10-27 1972
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4970 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	365	8-5/8	357	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 800', plug, 80 sx cement;
Fluid to 280', plug, 30 sx cement;
Fluid to 45', plug, 15 sx cement;

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1972
10-31-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
Address 701 First National Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF _____, SS.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of October, 1972

Ella Priess
Ella Priess Notary Public.

My commission expires August 25, 1976

DRILLERS' LOG

15-057-20041-0000

OKMAR OIL COMPANY
No. 1 Torline
C SW NW, Sec. 6-26S-21W
Ford County, Kansas

Elev: 2379 K.B.

Commenced: 10-16-72
Completed: 10-27-72

Surface Casing: 357' of
8-5/8" cemented w/225 sx
60-40 Posmix, 3%cc. 10-16-72

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 365
Shale	365 - 525
Shale & Sand	525 - 904
Blaine Anhydrite	904 - 920
Sand & Red Bed	920 - 1440
Stone Corral Anhydrite	1440 - 1472
Shale	1472 - 2135
Shale & Lime	2135 - 2280
Lime	2280 - 4550
Chert	4550 - 4600
Chert & Lime	4600 - 4640
Lime	4640 - 4970 T.D.

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1972
CONSERVATION DIVISION
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D. N. B. DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss.

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 30th day of October, 1972.

My Commission Expires:
August 25, 1976.

Ella Priess
Ella Priess, Notary Public