

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Ford County, Sec. 35 Twp. 26S Rge. 22W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Apache Oil Corporation  
Lease Name F. Temeat "A" Well No. 1  
Office Address 823 South Detroit, Tulsa 20, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 22 1959  
Application for plugging filed December 22 1959  
Application for plugging approved December 22 1959  
Plugging commenced December 22 1959  
Plugging completed December 22 1959  
Reason for abandonment of well or producing formation no oil and/or gas found  
in commercial quantities  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4972 Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	494'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 450'. Set Plug #1 at 450' with 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 at 35' cemented with 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.  
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R-R McNicol  
814 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 59

Darlene May  
Darlene May Notary Public.

My commission expires Sept. 30, 1963



15-057-00024-0000

R

CAPITT DRILLING, INC.

OPERATOR: Apache Oil Corporation  
F. Temaat "A" #1  
C SE NW Sec. 35-26S-22W,  
Ford County, Kansas

CONTRACTOR: Capitt Drilling, Inc.  
COMM: 12-3-59  
COMP: 12-22-59

Formations:

Sand	77'
Shale, Sand, Lime	385'
Shale	740'
Shale, Lime Streaks	1425'
Shale & Lime	1880'
Lime & Shale	2083'
Shale & Lime	2400'
Lime & Shale	2545'
Lime	3935'
Lime - Chalk	3987'
Lime & Shale	4100'
Lime	4840'
Lime & Shale	4871'
Lime & Chert	4902'
Lime	4915'
Lime & Chert	4930'
Lime	4972'

Rotary Total Depth (D&A) 4972'

Remarks: Set 8-5/8" surface casing  
at 494' cemented with 350  
sacks Surface Pozmix, 6%  
Strata Crete W/2% C.C.

We certify the above log is true and  
and correct to the best of our know-  
ledge and belief.

CAPITT DRILLING, INC.

*R.R. McNicol*

R. R. McNicol

RECEIVED  
STATE CORPORATION COMMISSION

AUG 4 1960

CONSERVATION DIVISION  
Wichita, Kansas