

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ford County, Sec. 24 Twp. 26S Rge. (E) 21(W)

Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Mull Drilling Company
Lease Name SPECK Well No. 1
Office Address 1625 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 8 1966
Application for plugging filed February 8 1966
Application for plugging approved February 8 1966
Plugging commenced February 8 1966
Plugging completed February 8 1966
Reason for abandonment of well or producing formation No oil or gas found in commercial quantities
If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas
Producing formation - - Depth to top - - Bottom - - Total Depth of Well 4841 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 700' with 35 sacks cement, plug @ 300' with 35 sacks cement, plug @ 45' with 15 sacks cement, 2 sacks in rathole. Plug down 6:00 a.m. 2-8-66.

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1966
2-14-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of February, 1966

My commission expires January 8, 1968

Shirley Keck
Notary Public.

ROTARY DRILLING LOG

15-657-30059.0000

Operator: Mull Drilling Company, Inc.
 #1 Speck
 C SE NE Section 24-26S-21W
 Ford County, Kansas

Contractor: Rains & Williamson Oil Co
 Commenced: 1-26-66
 Completed: 2-8-66

Remarks: Set 242' of 8-5/8" surface casing @ 249' with 225 sacks cement.

FORMATIONS:

Surface & Sand	40'
Shale	250'
Cement	249'
Shale & Shells	735'
Anhydrite Blaine	746'
Shale & Red Bed	1306'
Anhydrite	1342'
Shale	2270'
Lime & Shale	3035'
Shale & Lime Stks.	3185'
Lime & Shale	3450'
Shale & Lime	3565'
Lime & Shale	4210'
Lime	4350'
Lime & Shale	4408'
Lime	4540'
Lime & Shale	4595'
Lime	4705'
Lime & Shale	4765'
Lime	4784'
Shale	4789'
Lime	4841'
Rotary Total Depth (D&A)	4841'

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.


 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 10th day of February, 1966.

My Commission Expires:
 January 8, 1968


 Shirley Keck, Notary Public