

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155-21,063-  
0000

LEASE NAME Hill

WELL NUMBER 1

SPOT LOCATION SE SW NW

SEC. 12 TWP. 25 SRGE. 4W ~~XXXX~~(W)

COUNTY Reno

Date Well Completed 9-3-85

Plugging Commenced 9-3-85

Plugging Completed 9-3-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Associated Petroleum Consultants, Inc.

ADDRESS Suite 600, One Main Place, Wichita, KS 67202

PHONE # (316) 265-9385 OPERATORS LICENSE NO. 5601

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4160'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	272	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st plug @ 4100' w/ 40 sx, 2nd plug @ 800' w/ 35 sx, 3rd plug @ 320' w/ 40 sx, 4th plug @ 40' solid bridge w/ 25 sx, rathole 10 sx; 150 sx 60/40 poz, 2% gel, plug down @ 11:30 am 9-3-85


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc. License No. 5652  
Address P.O. Box 1609, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Gib Overbey (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gib Overbey  
Gib Overbey  
(Address) P.O. Box 1609, Great Bend, KS



SUBSCRIBED AND SWORN TO before me this 6th day of September, 1985

My Commission expires: August 25, 1987

Pamela K. Walters  
STATE CORPORATION COMMISSION PUBLIC  
Pamela K. Walters

SEP 9 1985 9-9-85

15-155-21063-0000

Office Phone  
(316) 792-7323

Mobile Phone  
792-1067

# MUSTANG DRILLING & EXPLORATION, INC.

P.O. Box 1609  
Great Bend, Kansas 67530

Associated Petroleum Consultants, Inc.  
Hill #1  
Reno County, KS

## DRILLERS LOG

Sand, Shale	0	276
Shale	276	625
Shale, Lime	625	905
Shale	905	995
Shale, Lime	995	1440
Shale, Sand, Lime	1440	1925
Shale, Lime	1925	2555
Shale	2555	2712
Shale, Lime	2712	2935
Lime	2935	3335
Lime, Shale	3335	3505
Lime	3505	3810
Shale, Lime	3810	3900
Shale, Lime, Sand	3900	3978
Lime, Shale	3978	4032
Shale, Lime	4032	4135
Lime	4135	4160
RTD		4160

RECEIVED  
STATE CORPORATION COMMISSION

SEP 9 1960

CONSERVATION DIVISION  
Wichita, Kansas