

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Reno

County. Sec. 14 Twp. 25S Rge. (E) 4 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner DeMier Oil Company

Lease Name Mount

Well No. 1

Office Address 2740 E. 41st St., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5/23/56 19

Application for plugging filed 5/23/56 19

Application for plugging approved 19

Plugging commenced 5/23/56 19

Plugging completed 5/23/56 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

X			

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation None Depth to top Bottom Total Depth of Well 4055 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
DRY HOLE						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 220'. Plug and solid bridge at this point. Then 25 sx
cement thru drill pipe. Mud to 15' then plug tied firmly to base and
10 sx cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Badger Drilling Co.

Address Great Bend, Kansas

STATE OF Okla., COUNTY OF Tulsa, ss.

Fred Demier

(employee or owner) (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

2740 E. 41st St., Tulsa 5, Okla.

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 56

My commission expires

Sept. 24, 1958

Notary Public.

PLUGGING

FILE SEC 14 T 25 R 4W
BOOK PAGE 64 LINE 43

15-155-00020-0000

De Mier Oil Company
Drillers Log - Mount #1
SW-SW-NW, Sec. 14, T-25S, R-4W
Reno County, Kansas


236.5' of 13 1/4" Casing set at 235'

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Remarks</u>
0	50'	Surface Soil and sand	
50'	160'	Shale and shells	
160'	235'	Blue shale and shells	Ran 236.5' of 13 1/4" casing set with 200 sacks.
235'	590'	Shale and shells	
590'	680'	Anhydrite streaks and shale	
680'	935'	Lime and shale	
935'	1110'	Shale and shells	
1110'	1465'	Lime and shale	
1465'	1680'	Lime, Shale and shells	
1680'	2060'	Lime and shale	
2060'	2095'	Lime	
2095'	2894'	Lime and shale	
2894'	3580'	Lime	Tops - Heb. 2518', B.L. 2706', L.K.C. - 2751' - Miss. 3528'
3580'	3615'	Lime and chert	
3615'	3795'	Mississippi Lime	
3795'	3829'	Lime and shale	
3829'	4035'	Lime	
4035'	4053'	Lime - sand	Total Depth - Dry

I certify the above to be a true and exact copy of the Drillers Log as shown by the Daily Drilling Reports.


BADGER DRILLERS, INC.

Subscribed and sworn to before me this 6th day of June, 1956.


NOTARY PUBLIC

My commission expires: 7-6-59

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1956
CONSERVATION DIVISION
WICHITA, KANSAS

6-19-56

PLUGGING
FILE SEC 14 T 25 R 4W
BOOK PAGE 64 LINE 43