

15-155-00358-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County, Sec. 15 Twp. 25 Rge. (E) 4 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines: NE/4

Lease Owner Phillips Petroleum Co.

Lease Name Tonn Well No. 1

Office Address Bartlesville, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 4-21-44 19

Application for plugging filed 4-22-44 19

Application for plugging approved 4-26-44 19


Plugging commenced 5-2-44 19

Plugging completed 5-6-44 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Viola Lime Depth to top 4008 1/2 DF Bottom 4010 DF Total Depth of Well 4011 DF Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Miss. Lime	Dry	3554		8 5/8"	289' (L.T.)	None
Viola Lime	Dry	4008 1/2	4011	5 1/2"	4005' (L.T.)	2887' 4"
Lans. K.C.	Dry	2752				
Misener	Dry	3981				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 6 sax cement on bottom, mudded to 235', dumped 15 sax @ 235', and filled w/mud to 5'. Dumped 5 sacks cement, filling to base of cellar.

15 25 4W
114 45

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to F. W. Shelton
Address Box 779 - Great Bend, Kans.

STATE OF Kansas, COUNTY OF Barton, ss.
F. W. Shelton (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. W. Shelton
STATE CORPORATION
Box 779 Great Bend Kans.

SUBSCRIBED AND SWORN TO before me this 20th day of June, 1944

My commission expires March 27, 1946. Notary Public.

Formation Record

Lease **Tonn**

Well No. **1**

FROM	TO	Formation	REMARKS
0	748	Shale & shells	
748	770	Anhydrite	
770	1690	Lime & shale	
1690	1905	Shale & shells	
1905	2045	Lime & shale	
2045	2160	Shale & shells	
2160	2845	Lime & shale	Top IEO 2752'
2845	3284	Lime	
3284	3343	Lime & shale	
3343	3450	Lime	
3450	3585	Lime & shale	Top Miss. Lime 3554'
3585	3658	Lime & chert	
3658	3674	Cherty shale	
3674	3861	Lime & chert	
3861	3870	Chert	
3870	3898	Lime & chert	
3898	3924	Lime & shale	
3924	4000	Shale	Top Missner 3981'
4000	4010DF	Lime	Top Viola 4008' D.F. w/show of oil in cuttings. Slight to good porosity. Set 3 1/2" csg to 4008', drld shoe, CO to TD 4010 w/no shows. Drld 1' deeper w/no shows. SP. Started up & had 300' WIH. Dumped 80 gal acid w/no increase. Treated w/500 gals acid, filled up 3071' WIH. Plugged back to 4008'. Perforated w/25 shots 4008' to 4008' no oil. Perforated w/15 shots from 3981-83 no oil. Peri w/22 shots from 3602 to 3610 no oil.

RECEIVED
 15-25-44
 114 45

