


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Edwards County, Sec. 35 Twp. 26S Rge. 17W (E)W (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Aurora & Anschutz
Lease Name #1 Fisher Well No. 1
Office Address 706 Union National Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 24, 19 54
Application for plugging filed September 24, 19 54
Application for plugging approved September 24, 19 54
Plugging commenced September 24, 19 54
Plugging completed September 24, 19 54
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4962 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	986'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to within 300' w/ heavy drilling mud - Ran
1/2 sack hulls and 20 sacks cement on bottom plug at 300'
Top plug set at 30' with 1/2 sack hulls and 10 sacks cement.
2:30 P.M. 19-24-54

RECEIVED
STATE CORPORATION COMMISSION
DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Anschutz Drilling Co., Inc. 9-28-54
Address 706 Union National Bank Building

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. G. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. G. Koelling*
706 Union National Bank Building (Address)

SUBSCRIBED AND SWORN to before me this 27th day of September, 1954

My commission expires July 28, 1958 *Charlene Barlow* Notary Public.

PLUGGING
BLK SEC 35 T 26 R 17W
PAGE 66 LINE 8

DRILLER'S LOG

Aurora & Anschutz
#1 Fisher
NE NE NE 35-26S-17W
Edwards County, Kansas

15-047-00090-0000

<u>TO</u>	<u>FROM</u>	
0	230	Clay & Shale
230	445	Shale & Sand
445	480	Lime & Stone
480	700	Red Rock & Sand Streaks
700	1000	Red Rock
1000	1127	Anhydrite & Red Rock
1127	1342	Shale
1342	1480	Shale & Shells
1480	1590	Salt & Shale
1590	2105	Shale & Shells
2105	2175	Lime & Shale
2175	2205	Lime
2205	2490	Lime & Shale
2490	2573	Lime
2573	3095	Lime & Shale
3095	3185	Lime
3185	3250	Sandy Shale & Lime
3250	3300	Lime & Shale
3300	3345	Lime
3345	3446	Lime & Shale
3446	3485	Shale & Lime
3485	3585	Lime
3585	3670	Shale & Lime
3670	3695	Lime & Shale
3695	3914	Lime
3914	3985	Lime & Shale
3985	4025	Shale & Lime
4025	4048	Lime & Shale
4048	4135	Lime
4135	4190	Lime & Shale
4190	4378	Lime
4378	4540	Lime & Shale
4540	4550	Lime, Shale & Chert
4550	4565	Shale & Lime
4565	4585	Shale & Sand
4585	4620	White Sand & Shale
4620	4640	Sand
4640	4685	Sand, Shale, Lime & Chert
4685	4715	Lime
4715	4755	Lime & Chert
4755	4790	Lime
4790	4813	Chert & Lime
4813	4870	Lime
4870	4900	Sand & Shale
4900	4922	Lime, Shale & Sand
4922	4962	Arbuckle
	4962	ROTARY TOTAL DEPTH

COMMENCED: 8-31-54
COMPLETED: 9-23-54

CASING RECORD:

Set 986' of 8 5/8" surface casing with 425 sacks of cement.

D & A

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION
OCT - 1 1954 10-1-54
CONSERVATION DIVISION
Wichita, Kansas

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Fisher located NE NE NE of Section 35-26S-17W, Edwards County, Kansas.

PLUGGING
NE NE NE 35-26S-17W
WELL NO. 166 LINE 8

ANSCHUTZ DRILLING CO., INC.

BY: *E. G. Koelling*
E. G. Koelling

Subscribed and sworn to before me this 28th day of September, 1954.

My Commission Expires: July 28, 1958

Charlene Barlow
Notary Public