

15-047-00058-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Edwards County. Sec. 35 Twp. 26S Rge. 17 (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner D. R. Lauck Oil Company, Inc.

Lease Name Fisher Well No. 1

Office Address 301 South Broadway Wichita 2 Kans

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed September 6, 19 57

Application for plugging filed " 6, 19 57

Application for plugging approved " 6, 19 57

Plugging commenced " 6, 19 57

Plugging completed " 6, 19 57

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well N.A. Reeves

Producing formation Depth to top Bottom Total Depth of Well 4755 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	233'	8 5/8"	233'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud 4755 - 225
 plug 225 - 221
 cement 221 - 181
 mud 181 - 35
 plug 35 - 31
 cement 31 - 6 bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Cementing Company

Address Great Bend Kansas

STATE OF Kansas COUNTY OF Sedgwick ss. John H. Knightley


(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. (So help me God)

(Signature) John H. Knightley Wichita Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 57

My commission expires Sept. 14, 1959

Elizabeth Gray Notary Public.



PLUGGING
FILE SEC. 35 T. 26 R. 17W
BOOK PAGE 43 LINE 37

15-047-00058-0000

D. R. Lauck Oil Company, Inc.

Fisher #1

NW NW NW Sec. 35-26S-17W
Edwards County, Kans

Commenced: August 21, 1957
Completed: Sept. 6, 1957

Casing Record: 233' 8 5/8" cem.w/250 sacks

Elevation: GR 2124; DF 2127; KB 2129

Drillers Log

Sand & clay	200
shale	335
sand	365
red bed	1100
shale & shells	1390
Anhydrite	1400
Shale & shells	2125
shale & lime	2595
lime)broken)	2650
shale & lime	2690
sandy shale & lime	2795
lime & shale	3195
shale	3305
shale & lime	3480
broken lime & shale	3600
lime & shale	3775
lime (chalky)	3880
lime	3948
shale & lime	4034
lime	4339
lime & shale	4366
lime	4422
lime & shale	4485
lime	4578
Mississippian	4606
sand & shale	4630
Kinderhook	4650
Viola chert	4658
Lime shale & chert	4704
lime & chart	4720
chert	4755

	<u>Sample</u>	<u>Tops</u>	<u>Schlumberger</u>
Heebner	3894-1765		3894-1765
Douglas	3933-1804		3934-1805
Brown Lime	4035-1906		4036-1907
Lansing KC	4053-1924		4054-1925
Base Kansas City	4406-2277		4406-2277
Mississippian	4557-2428		4554-2425
Kinderhook shale	4588-2459		4576-2447
Kinderhook sand	4593-2464		4596-2467
Viola	4696-2567		4694-2565
Rotary Total Depth	4755-2626		4756-2627

DST #1 (M-D) 4594-4610 Open 1 hour;
weak blow 1 hour; recovered
30' mud BHP 552#-20 min.

D & A

RTD

9-11-57

STATE CORPORATION COMMISSION

SEP 11 1957

COMMISSION DIVISION
Topeka, Kansas

PLUGGING	
FILE SEC	35 T. 26 R. 17W
BOOK PAGE	43 LINE 37