

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-21, 015-6006

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Gear Petroleum Inc.

Complete Address 300 Sutton Place Wichita Kansas 67202

Lease Name Lisher Well No. A2-15

Location N/2 of N/2 of SE/4 Sec. 15 Twp. 26 Rge. 17 (East)(West)

County Edwards Total Depth 4700'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co.

Address 1720 Kansas State Bank Bldg, Wichita, Kansas 67202 License No. _____

Operation Completed: Hour: 3:00 P.M. Day: 3 Month: April Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 1162'. 1st plug at 1080' with 60 sbs of cement. 2nd plug pushed rubber plug to 275' and pumped 40 sbs of cement on top of it. 3rd plug 40' to 0' on solid bridge with 100 sbs of cement. Then they circulated 10 sbs of cement in rat hole & put 3 sbs of cement in water well. The well was plugged through drill pipe with hole full of heavy mud. The plugging was accomplished by Allied Cementing Co. Inc.

RECEIVED
STATE CORPORATION COMMISSION

Amount of Surface Casing: 289' of 8 1/8" Cement Circulated APR - 0 1982 4-6-82

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 4-12-82
INV. NO. 9895-12

Signed: _____
Conservation Division Agent