

KANSAS

Form CP-3
Rev. 6-4-68

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Drlg. Co. Inc. 15-047-20087-0000

Complete Address 800 Bitting Bldg. Wichita, Ks

Lease Name Fisher Well No. 1

Location C/NE/SW Sec. 15 Twp. 26 Rge. 17 (E) (W) W

County Edwards Total Depth 4593

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Ralph Comstock Pipe Pulling Inc.

Address Stafford, Ks 320 S. Park License No. 490

Operation Completed: Hour 1:30 PM Day 24 Month 3 Year 1971

The above well was plugged as follows:

310 ft of 8 5/8 surface pipe cemented with 250 sacks. 4593 ft of

5 1/2 long string cemented with 100 sacks. Top perf. 4553 ft. Sand

back to 4530 ft, 5 sacks cement with bailer. Pulled 2400 ft of 5 1/2.

Pumped 2 sacks hulls, 15 sacks gel., & 100 sacks cement to surface.

Pumped by Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: G. Russell Bihentor
Well Plugging Supervisor

DATE 3/26/71
INV. NO. 3460-W