

15-047-10116-0006

Form CP-3
Rev. 6-9-67

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1967
7-13-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued June 22, 1967.

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address Box 562, Great Bend, Kansas 67530

Lease Name Mathes Well No. # 1

Location C SW SW NW Sec. 13 Twp. 26 Rge. 17 (E) (W) W

County Edwards Total Depth 4697'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Santa Fe Pipe & Supply, Inc.

Address Box 562, Great Bend, Kansas 67530 License No. 574

Operation Completed: Hour 2:30 P.M. Day 12th Month July Year 1967

The above well was plugged as follows:

300' of 8 5/8" surface pipe, cemented with 240 sacks. 4631' of 5 1/2" long
string, cemented with 100 sacks. Plug back T.D. 4595'. Top perforation
4525'. 10 sacks of cement was pumped on bottom with the top of the cement
at 4450'. 2688' of 5 1/2" long string was recovered from the hole. Bridge plug
was pushed in fluid to 280', bridge plug and rock bridge from 280' to 270'.
5 sacks of cement was mixed in a barrel, and put on plug at 270', through
the dump bailer, and let set over-night. Next day hole was bailed dry, and
20 sacks of cement was added to the plug. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/13/67
INV. NO. 5960-W