

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1976

CONSERVATION DIVISION
Wichita, Kansas

1-15-76

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drlg Co 15.047-20180-0000

Complete Address 617 Union Center Wichita, KS

Lease Name Roenbaugh Well No. 1

Location C SW/NW Sec. 9 Twp. 26 Rge. 17 (E) (W) W

County Edwards Total Depth 4710

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 11:00 AM Day 13 Month 1 Year 1976

The above well was plugged as follows:

252 ft 8 5/8 surface cemented with 225 sacks. 3293 ft 4 1/2 long string
cemented with 100 sacks. Top perf. 3177 ft. Sand to 3150 ft, 4 sacks
cement with bailer. Pulled 2785 ft 4 1/2. Pump 2 sacks hulls, 10 sacks
gel, 100 sacks cement to surface.

Pumped by Allied Cementing Great Bend, KS

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 1-15-76

INV. NO. 2569-W

Signed Russell B. Bunker
Well Plugging Supervisor