

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 23, 1968.

Operator's Full Name Glen Rupe 15-047-20024-0000

Complete Address: 222 Brown Bldg., Wichita, Kansas 67202

Lease Name Michaelis Well No. # 1

Location C NE NW Sec. 13 Twp. 26 Rge. 19 (E) (W) W

County Edwards Total Depth 4850'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza Bldg., Wichita, Kans. 67202 License No. _____

Operation Completed: Hour 3:30AM Day 8th Month March Year 1968

The Above well was plugged as follows:

290' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid level in the hole was at 100'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 275', and cemented with 25 sacks, through the drill pipe, with cement from 275' to 200'. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks, with cement from 30' to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/11/68

INV. NO. 1386-W

Signed: Arlene Elving
Well Plugging Supervisor