

*15-047-60253-0000*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 22 1963

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Sunray DX OIL Co.

Complete Address: 321 W. Douglas, Wichita 2, Kansas

Lease Name Gus Edwards Well No. # 1

Location C SW SW Sec. 35 Twp. 26 Rge. 19 (E) (W) W

County Edwards Total Depth 5012

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 3:00PM Day 19th Month April Year 1963

The Above well was plugged as follows:

329' of 8 5/8" surface pipe cement circulated. 5004' of 5 1/2" long string  
cemented with 300 sacks. Plugged back to 4219'. Perferated 4196' to 4202'.  
Sanded to 4180' cemented with 5 sacks. Hole was filled to 225', 10' rock  
bridge, cemented with 20 sacks. Hole was filled with mud to 40', 10' rock  
bridge, cemented with 10 sacks to base cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 4/18/63

INV. NO. 6917-W