

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 30-1LOCATION CNE NW SESEC. 28 TWP. 25 RGE. 12WDry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease BonhamOperator Plains Exploration Address Denver 2, ColoradoField \_\_\_\_\_ County StaffordTotal Depth 4216 Feet.

(Describe briefly the manner in which the well was plugged)

Lane wells plug at 4160 feet cement to 4152 feetdumped with bailer. Lane wells plug at 4080 feetcement to 4072 feet dumped with bailer. Sand to 4032feet and cement to 4016 feet dumped with bailer.Sand to 3612 feet and cement to 3596 feet dumped withbailer. Halliburton filled hole with heavy mud to 190 feet.Halliburton pumped cement from 190 feet to 120 feet  
~~followed with heavy mud. 15' of cement in top of~~  
 surface pipe to base of cellar.H. W. KerrDistrict Conservation AgentDate October 18, 1945.