

15-185-01426-0000

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1963
10-8-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Clinton Oil Co. & Navajo Drilling Co.

Complete Address: 6810 W. Highway 54, Wichita, Kansas

Lease Name Green Well No. # 1

Location NE NE SW Sec. 33 Twp. 25 Rge. 12 (E) (W) W

County Stafford Total Depth 4265

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Navajo Drilling Co.

Address: 205 Central Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 4:30AM Day 5th Month Oct. Year 1963

The Above well was plugged as follows:

222' of 8 5/8" surface pipe, cemented with 200 sacks. Fluid was up in
the hole. 1st cementing plug and 1/2 sack hulls was pushed to 240', cement-
with 35 sacks, through drill pipe. Hole was filled with drilling mud to
40', 2nd cementing plug, bridged with 1/2 sack hulls, cemented with 10
sacks to base cellar. Rat hole bridged and cemented with 5 sacks.
This cementing job was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 10/10/63
INV. NO. 4890-4

Signed: Archie Elving
Well Plugging Supervisor