

15-185-11896-0000

Form CP-3
Rev. 6-26-62

H
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1963

4-26-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name R. P. Nixon

Complete Address: 754 E. Wichita St. Russell, Kansas

Lease Name Slade Well No. # 1

Location C S/1/2 SW NW Sec. 35 Twp. 25 Rge. 12 (E) (W) W

County Stafford Total Depth 4141

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen and Smith

Address: 204 E. Sixth St. Ellinwood, Kansas License No. 396

Operation Completed: Hour 3:00PM Day 22nd Month April Year 1963

The Above well was plugged as follows:

404' fo 10 3/4" surface pipe cement circulated. 4139' of 7" long string.
Plugged back to 3840'. Perferated at 3640' to 45'. Pushed plug to 3640',
cemented with 5 sacks. Plug was set at 235' with 20' rock and mud bridge
to seal off fluid. Hole was bailed down, and cemented with 25 sacks.
Hole was filled to 40' with mud, 10' rock bridge, cemented with 15 sacks
to base cellar.
3133' of 7" long string recovered from hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/26/63

INV. NO. 6964-11