

P

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 185 20,436-A (of this well)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 02 1978  
2-2-78

Operator's Full Name L. D. Davis  
Complete Address Box 324 - At., Bend, Kansas 67530  
Lease Name Stanley Well No. 1  
Location SE - NW - SW - Sec. 5 Twp. 25 Rge. 12 (E) (W) X  
County Stafford Total Depth 4217  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Falso Casing Pulling  
Address Box 176 Chase, Kansas 67524 License No. 683  
Operation Completed: Hour 1:45 pm Day 31 Month Jan Year 1978

The above well was plugged as follows:

258' 8 5/8" casing w/ 150 sack cement - 5 1/2" casing set @ 4216'  
w/ 125 sack cement - prof 3976' to 83' plug back to 3950' sand back  
to 3725' mix & dump 5 sack cement w/ dump barrel - mix & pump  
3 sack hulls - 20 gal. release plug - mix & pump 100 sack cement  
374.1 37 C.C. to top of casing - shut in w/ 200# pressure  
Recovered - 2014' 5 1/2" casing -  
Pumped by -  
Allied Cementing Co. At., Bend, Ks - 67530

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 2-3-78

INV. NO. 6700-W