

AM 4-4313

15-047-00275-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1964
9-16-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name James W. Hershberger

Complete Address: 807 First National Bank Bldg., Wichita, Kansas

Lease Name Herrmann Well No. # 1

Location C SE SW Sec. 19 Twp. 25 Rge. 20 (E) (W) W

County Edwards Total Depth 4800

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 5:00AM Day 15th Month Sept. Year 1964

The Above well was plugged as follows:

308' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fluid
level in the hole was at 130'. 1st cementing plug and 1/4 sack of hulls
was pushed in fluid to 275', and cemented with 35 sacks, through the
drill pipe. Hole was filled with drilling mud to 40'. 2nd cementing
plug, bridged solid with hulls, on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
5 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/16/64
INV. NO. 9819-W

Signed: Archie Elving
Well Plugging Supervisor