

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

OCT 21 1966
10-21-66
CONSERVATION DIVISION
WICHITA, KANSAS

15-047-30072-0000

Operator's Full Name Walters Drilling Company & Mull Drilling Company

Complete Address: ~~510 Orpheum Bldg.~~
400 Insurance Bldg., Wichita, Kansas

Lease Name Einsel-Edwards Well No. # 1

Location C NW NE Sec. 32 Twp. 26 Rge. 20 (E) (W)W

County Edwards Total Depth 4933'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Walters Drilling Company

Address: ~~510 Orpheum Bldg.~~
400 Insurance Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 9:45PM Day 19th Month Oct. Year 1966

The Above well was plugged as follows:

465' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid level in the hole was at 125'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 400', and cemented with 25 sacks at 400', through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aubie Elving
Well Plugging Supervisor

DATE 10/21/66
INV. NO. 4442-4