

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1966
9/23/66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company 15-057-30055-0000

Complete Address: 1625 Wichita plaza, Wichita, Kansas

Lease Name Wetzel Well No. 1

Location C SW SW Sec. 2 Twp. 26 Rge. 21 (EX) (W)

County Ford Total Depth 4850'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 4:30PM Day 20 Month 9 Year 1966

The Above well was plugged as follows:

8 5/8" to 287' circulated w/ cement. 4 1/2" to 4849' Cemented

Top perforations 4770' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4700' Mud 4700' to 700'

Spotted 25 sacks cement 700' to 625' Mud 625' to 280'

Spotted 20 sacks cement 280' to 220' Mud 220' to 35'

Plug, Hulls & 10 sacks cement: 35' to 0'.

Globe cementing Pump Truck. Pulled 3000' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/26/66
INV. NO. 3975-u

Signed: Edmond J. Fiso
Well Plugging Supervisor