

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company Inc. 15-057-30063-0000

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Rehment Well No. 1

Location C NW SE Sec. 2 Twp. 26 Rge. 21 (NE) (W)

County Ford Total Depth 4810'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Rains & Williamson Drilling Co.

Address: 1425 Wichita Plaza, Wichita Kansas License No.

Operation Completed: Hour 6:30PM Day 4 Month 9 Year 1966

The Above well was plugged as follows:

8 5/8" to 288' circulated w/ cement. T.D. 4810'

Mud 4810' to 700' Spotted 30 sacks cement 700' to 600'

Mud 600' to 330' Spotted 35 sacks cement 330' to 230'

Mud 230' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

Globe Cementing Pump Truck.

RECEIVED
STATE CORPORATION COMMISSION

SEP 7 1966
9-7-66

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/7/66

INV. NO. 3878-w

Signed: [Signature]
Well Plugging Supervisor

ROTARY DRILLING LOG

15-057-30063-0000

Operator: Mull Drilling Company, Inc.
 #1 Rehmert
 C NW SE Sec. 2-26S-21W
 Ford County, Kansas

Contractor: Rains & Williamson Oil Co.
 Commenced: 8-25-66
 Completed: 9-4-66
 Remarks: Set 288.63' of 8-5/8" surface pipe with 200 sacks GL3.

FORMATIONS:

| | |
|--------------------------|-------|
| Soil Clay Shale | 150° |
| Shale | 762° |
| Anhydrite | 773° |
| Shale | 1327° |
| Anhydrite | 1367° |
| Shale | 1680° |
| Shale w/Lime | 2295° |
| Shale & Lime | 2685 |
| Lime | 2995° |
| Lime & Shale | 3165° |
| Shale & Lime | 3465° |
| Shale | 3830° |
| Shale & Lime | 3910° |
| Lime & Shale | 4165° |
| Lime | 4635° |
| Lime & Shale | 4690° |
| Lime | 4810° |
| Rotary Total Depth (D&A) | 4810° |

RECEIVED
 STATE CORPORATION COMMISSION

SEP 16 1966

CONSERVATION DIVISION
 (Wichita, Kansas)

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 6th day of September, 1966.

My Commission Expires:
 3-3-70

Mary J. Brown
 Mary J. Brown Notary Public