

15-047-00274-00-00

Form CP-3
Rev. 6-26-62

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

SEP 8 1964
9-8-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 321 West Douglas, Wichita, Kansas

Lease Name Leona Butler Well No. # 1

Location C NE SE Sec. 7 Twp. 25 Rge. 20 (E) (W) W

County Edwards Total Depth 4863

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Stickle Drilling Company

Address: 1100 Bitting Bldg., Wichita, Kansas License No.

Operation Completed: Hour 1:30AM Day 6th Month Sept. Year 1964

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level was up in the hole. 1st cementing plug and 1/2 sack hulls was push-
ed in fluid to 245', and cemented with 35 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls, on fluid at 40', and cemented with 10 sacks to the
base of the cellar.

Rat and mouse hole bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company,

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/8/64

INV. NO. 9984-W