

15-047-30065-00-00

Form CP-3
Rev. 6-26-62

9

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 31 1966
1-31-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jay Bergman Oil Company & Kenneth Rupp

Complete Address: 425 Union Center Bldg., Wichita, Kansas

Lease Name I. E. Smith Well No. # 1

Location C NE SE Sec. 34 Twp. 25 Rge. 19 (E) (W) W

County Edwards Total Depth 4736'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Bergman Drilling, Inc.

Address: 425 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 10:00PM Day 26th Month Jan. Year 1966

The Above well was plugged as follows:

298' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 275', 1st cementing plug, bridged with
hulls on fluid at 275', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged with hulls on
fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 1-31-66

INV. NO. 2667 W