

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 047-20368-00-00 (of this well)

Operator's Full Name Sheeler Oil Co.  
Complete Address 4867 S. Sheridan St. #701 Tulsa Okla, 74145  
Lease Name Entrada Tract Well No. 2  
Location SW-SE-NE- Sec. 36 Twp. 25 Rge. 18 (E) (W) X  
County Edwards Total Depth 4575  
Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A         
Other well as hereafter indicated       

Plugging Contractor Felso Casing Pulling  
Address Box 176 Chas. Kans. 67524 License No. 683  
Operation Completed: Hour 4 pm Day 6 Month 11 Year 1978

The above well was plugged as follows:

304' 8 5/8" Casing w/ 180 sac Cement - 4 1/2" Casing set @ 4573' w/  
175 sac Cement - top perf. 4554' - Sand back to 4500' top  
sand w/ 4 sac mixed Cement w/ dump. bit hole push  
3620' - 4 1/2" Casing - Mix. & pump in 8 5/8" Casing - 3 sac bulls - 20  
sac gel - release plug - Mix. & pump 125 sac 60/40 gas  
Cement w/ 27 gal. - 370C to top of Casing Shut in w/ 200 lbs  
Pumped by  
Alford

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 11-14-78 NOV - 9 1978  
INV. NO. 8508-00 11-9-78  
CONSERVATION DIV. Sec.  
Wichita, Kansas