

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

July 14, 1973

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

7-20-73

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling Co., Inc. has this  
date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Hershberger Enterprises, Inc.

Complete Address: Suite 230-200 W. Douglas, Wichita, Kansas 67202

Lease Name: Friesen "A" Well No. 1

Location: NW NW SW Sec. 29 Twp. 24 Rge. 7 (E) (W) X

County: Reno Total Depth 2110' Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Cameron was instructed to plug the well as follows:

Fill hole with mud. Push plug and  $\frac{1}{2}$  sack hulls to 400' and pump 35  
sacks cement through drill pipe at 400'. Pump 25 sacks cement through  
drill pipe at 195'. Push plug and  $\frac{1}{2}$  sack hulls to 40' and cap hole  
with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

*Arthur J. Lawrence*  
Conservation Division Agent