



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JAN 31 1966  
1-31-66  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. O. C. Arnott of Bergman Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Arnott guarantees payment of the plugging fee.

Operator's full Name: Jay Bergman Oil Co., & Kenneth Rupp

Complete Address: 425 Union Center Bldg., Wichita, Kansas

Lease Name: I. E. Smith Well No. # 1

Location: C NE SE Sec. 34 Twp. 25 Rge. 19 (E)(W) W

County Edwards Total Depth 4736' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Arnott was instructed to plug the well as follows:

298' of 8 5/8" surface pipe, cement circulated with 225 sacks.

Fill hole with drilling mud to 275', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent