

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 31 1963

1-31-63

CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Webb Hill of Mack Oil Co. has this

date requested permission to plug the following described well:

Mr. Webb Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name: Isern Well No. # 1

Location: C SW SW Sec. 4 Twp. 25S Rge. 20 (E) (W) W

County Edwards Total Depth 4783 Oil Well

Gas Well  Input Well  SWD Well  D & A x Lost Hole

Mr. Hill was instructed to plug the well as follows:

268' of 8 5/8" surface pipe circulated with 200 sacks cement.  
Fill hole to 180' with heavy mud, 1/4 sack hulls, 1st cementing  
plug with 20 sacks cement. Fill hole with heavy mud to 40',  
1/4 sack hulls. 2nd cementing plug with 10 sacks cement to base  
of cellar. Rat and mouse hole bridged and cemented with 4 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent