

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 24 1966
10-24-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Curley Brau of Edmiston Drilling Co., Inc as this
date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Ks.

Lease Name: Alspaugh Well No. # 1

Location: C NW NE Sec. 15 Twp. 25 Rge. 20 (E)(W) W

County Edwards Total Depth 4706' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

267' of 8 5/8" surface pipe, cement circulated with 185 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack
of hulls on fluid at 250', and cement with 25 sacks. Fill hole with drill
ing mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cem-
ent with 10 sacks to base of cellar. Bridge and cement rat hole with 2
sacks.

Very truly yours,

Archie Elving
Conservation Division Agent