



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 23 1963
 1-23-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. George Nichols of Braden Drilling Co. has this date requested permission to plug the following described well:

Mr. George Nichols guarantees payment of the plugging fee.

Operator's full Name: Braden Drilling Co.

Complete Address: 1206 Union National, Wichita, Kansas

Lease Name: Clara Well No. # 1

Location: NE NE SE Sec. 32 Twp. 25 Rge. 17 (E) (W) W

County Edwards Total Depth 4675 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nichols was instructed to plug the well as follows:

326' of 8 5/8" surface pipe circulated with 275 sacks cement. Fill hole with heavy mud to 180', 1/2 sack hulls, 1st cementing plug with 20 sacks cement. Fill hole with heavy mud to 40', 1/2 sack hulls 2nd cementing plug with 10 sacks cement, to base cellar. Rat hole bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent