

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
NOV 20 1967
11-20-67
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 11, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. H. G. Pankratz of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: Richard S. Davis

Complete Address: 1023 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name: Freddie Yoder Well No. 1

Location: C E/2 SE SE Sec. 28 Twp. 24 Rge. 5 (E) (W) X

County Reno Total Depth 3193' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and 1/4 sack hulls to 240' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent