

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

August 14, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1970
CONSERVATION DIVISION
Wichita, Kansas

8-17-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Damme of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Damme guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Company

Complete Address: 1016 Union Center, Wichita, Kansas 67202

Lease Name: Garver Well No. 1

Location: NW SW SE Sec. 28 Twp. 24 Rge. 5 (E) (W) X


County: Reno Total Depth 3815' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Damme was instructed to plug the well as follows:

Fill hole with mud to 215'. Push plug and 1/4 sack hulls to 215' and
cement hole with 35 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cement hole to cellar
with 15 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent