

State of Kansas



FORM CP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

December 21, 1981

*Rec'd  
1-12-82*

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Jim Eubanks of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Ram Petroleum Corporation  
Complete Address: 500 Vickers Kansas State Bank & Trust Bldg, Wichita, Ks. 67202  
Lease Name: Warnken Well No. 1  
Location: SE SW SW Sec. 8 Twp. 24 Rge. 7 (E) (W)  
County: Reno Total Depth: 2843'


Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: No Title (Abstract not in order)

Mr. Eubanks was instructed to plug the well as follows:

8 7/8" - 328' - 225 sacks cement 2% gel 3% cc. Fill hole with mud.  
Pump 50 sacks cement through drill pipe at 350'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent