

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Edwards County. Sec. 17 Twp. 25 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner Aurora Gasoline Company, Etal

Lease Name Hupp Well No. 1

Office Address 802 Union Natl. Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Nov. 25 1956

Application for plugging filed " 19"

Application for plugging approved " 19"

Plugging commenced " 19"

Plugging completed " 19"

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4650 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	250	8 5/8"	245'	None
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud from 4650 to 250': permanent bridge at 250' cemented with 20 sacks of cement:

Mud to 35': Pushed plug down, and cemented with 10 sacks of cement cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rex & Morris Drilling Company

Address Box 334, El Dorado, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 31 1956  
CONSERVATION DIVISION  
WICHITA, KANSAS

STATE OF Kansas COUNTY OF Butler, ss.  
C. E. McClure (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure

Box 334, El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of December, 1956

My commission expires July 23, 1960

Winifred E. Cruik  
Winifred E. Cruik

Notary Public.

PLUGGING  
FILE SEC. 17 T. 25 R. 17 W  
BOOK PAGE 119 LINE 21

HUPP WELL # 1

AURORA GASOLING COMPANY & REX & MORRIS DRILLING COMPANY

Total Depth - 4650  
Contractor - Rex & Morris Drilling Co.  
Commenced - 11-11-56  
Completed - 11-25-56  
Initial Production - D & A

Location - SW SW SE  
Section - 17-25S-17W  
Edwards County, Kansas

Casing Record:  
8 5/8" @ 245.5 w/ 200 sacks

FORMATION	DEPTH
Surface Hole	250
Shale	350
Sand & Shale	525
Red Bed Shale	1158
Annydrite	1180
Shale & Shells	1400
Salt & Shale	1650
Shale & Shells	1800
Shale & Lime	2050
Lime & Shale	3760
Lime	3853
Lime & Shale	3933
Shale & Lime	3972
Lime	4318
Lime & Shale	4407
Shale & Lime	4458
Chert	4479
Conglomerate	4540
Shale & Lime	4586
Lime & Shale	4602
Shale & Lime	4639
Lime	4650

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By C. E. McClure *C. E. McClure*

~~Title XXX Geologist~~ Office Mgr.

STATE OF KANSAS )  
                          ) SS.  
COUNTY OF BUTLER )

Subscribed and sworn to before me, a Notary Public, this 4<sup>th</sup> day of December, 1956.

Winfred E. Omit  
Notary Public

My commission expires:

July 23 1960

RECEIVED  
STATE CORPORATION COMMISSION

DEC 5 1956

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 17 T 25 R 17W  
BOOK PAGE 119 LINE 21