

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 17 Twp. 25 Rge. 17W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SE NW


Lease Owner F & M Oil Company, Inc.
Lease Name S H & H Farms Well No. 1
Office Address 422 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 11-30 1979
Application for plugging filed 11-30 1979
Application for plugging approved 11-30 1979
Plugging commenced 11-30 1979
Plugging completed 11-30 1979

Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens - Pratt, Ks.
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4615'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	355'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

50 sks. @ 360'
10 sks. @ 40'
5 sks. @ in rathole
1 sk. in water well

50-50 Pozmix, 4% Gel, By Sun Cementing. Job Complete @ 10:15 a.m..

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1979
12-10-79
CONSERVATION DIVISION
STATE OF KANSAS


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company
P. O. Box 1389, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
Allen Drilling Company (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Dale L. Smith
P. O. Box 1389, Great Bend, Kansas 67530
(Address)



SUBSCRIBED AND SWORN TO before me this 6th day of December, 1979

Ulaida Nichols
Notary Public.

My commission expires 1-28-1980

DRILLER'S WELL LOG

DATE COMMENCED: 11-23-79
DATE COMPLETED: 11-30-79

F & M Oil Company, Inc.
S H & H Farms #1
C SE NW, Sec. 17-25-17W
Edwards County, Kansas

ELEVATIONS K.B.
G.L.

FORMATION DATA

3847-3852' Shale
3852-3865' Lime
3865-3879' Lime
3879-3977' Shale
3977-3988' Lime and Shale
3988-4295' Lime
4295-4461' Lime and Shale
4461-4528' Sand
4528-4568' Chert and Lime
4568-4615' Shale
4615' T.D.

Anhydrite
Heebner 3847
Toronto 3865
Douglas 3879
Brown Lime 3977
Lansing 3988
Base K. C. 4295
Cherokee 4461
Cherokee Sand None
Mississippi 4528
Kinderhook 4568
T.D. 4615

SURFACE PIPE:
Ran 12 Jts. Used 28# 8 5/8" Casing.
Tally 351'. Set @ 355' w/325 sks.
60-40 Pozmix, 2% Gel, 3% c.c.
By Sun Cementing. P.D. 11:30 p.m.
Cement Circ.

PLUGGING:
50 sks. @ 360'
10 sks. @ 40'
5 sks. in rathole
1 sk. in water well
50-50 Pozmix, 4% Gel. By Sun Cementing.
Job completed @ 10:15 a.m.
State Plugger - Bill Owens
Pratt, Kansas

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1979
CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON) ss.

DALE L. SMITH, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Dale L. Smith

Subscribed and sworn to before me this 6th day of December 1979.



Wanda Nichols
(Notary Public)

My commission Expires: 1-28-1980