

15-047-00121-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 12/28/87

LEASE NAME Fatzer

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 34 TWP 25 RGE. 17W (or (W))

COUNTY Edwards

Date Well Completed

Plugging Commenced 1/27/88

Plugging Completed 2/9/88

LEASE OPERATOR Gas Marketing, Inc.

ADDRESS Box 159, Stafford, KS 67578

PHONE#(316) 234-5191 OPERATORS LICENSE NO. 6981

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dist #1 Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4615'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	260'	NONE
				4 1/2"	4615'	2428'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 4020' and 4 sacks of cement. Shot pipe @ 2830', 2428', and pulled 77 joints of 4 1/2" casing. Used Allied to plug surface with 4 hulls, 10 gel, 50 sacks cement, 10 gel, 1 hull, 8 5/8" plug, and 125 sacks of cement, 60/40 poz/6% gel. Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address Box 347, Chase, KS 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereinafter contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) BX 347, Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 10 day of February, 19 88

Jessie Hoover
Notary Public

My Commission Expires:



2-11-88
Form CP-4
Revised 07-86

WELEX



RADIATION GUARD LOG

NORTHERN NATL. GAS
 COMPANY PROD. CO. NATIONAL
 DRILLING CO. INC. & B.O.A.
 WELL FATZER #1

WILDCAT
 EDWARDS
 KANSAS
 FIELD County State File

COMPANY NORTHERN NATURAL GAS PRODUCING
 NATIONAL DRILLING CO. INC. & B.
 WELL FATZER #1
 FIELD WILDCAT
 COUNTY EDWARDS STATE KANSAS
 PROPERTY OF
 K. G. S. LIBRARY
 540 Petroleum Bldg.
 Wichita, Kansas 6720

Location C - SW - SW
 Sec. 34 Twp 25S Rge 17W

Permanent Datum KELLY BUSHING Elev. 2129'
 Log Measured From KELLY BUSHING
 Drilling Measured From KELLY BUSHING

Type Log	GAMMA	NEUTRON	GUARD
Run No.	ONE	ONE	ONE
Date	4-4-60	4-4-60	4-4-60
Total Depth Driller	4632'	4632'	4632'
Total Depth Welox	4632'	4632'	4632'
Survey Begins	4622'	4632'	4627'
Survey Ends	0'	0'	3800'

Mud Data:
 Type Fluid in Hole WATER BASE
 Salinity PPM STARCH MUD
 Weight lb./gal. 18%
 Viscosity 10.3
 pH 52
 Loss cc. 30 min. F 6.5 F
 Res. Surface Temp. F 11.6 F
 Res. Max. Hole Temp. F 114.60 F
 Fluid Level FULL
 Source Mud Sample FLO LINE

Recorded By R. SNOOK
 Witnessed By BILL IVERSON

BORE HOLE RECORD				CASING RECORD	
Run	Bit	From	To	Size	Wat From
ONE	12-1/4"	260'	0'	8-5/8"	260'
TWO	7-7/8"	4632'	260'		

RECEIVED
 STATE CORRELATION COMMISSION

DEC 30 1961

CONSERVATION DIVISION
 WICHITA, KANSAS