

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20,242-

LEASE NAME Pearce

WELL NUMBER #1

SPOT LOCATION SW NW SW

SEC. 36 TWP 25 RGE 17 (E) of (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 10-28-85

Plugging Completed 11-8-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR White and Ellis Drilling, Inc.

ADDRESS 401 E. Douglas Suite 500.
Wichita, Kansas 67202

PHONE # 316-549-6508 OPERATORS LICENSE NO. 5420

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	327'	None
				4-1/2"	4599'	544.65'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 4440' and 4 sacks cement. Pulled 17 joints of 4-1/2" casing. Squeezed well with 1 sack hulls, 5 sacks gel, 50 sacks cement, released plug and pumped 150 sacks of 60/40 pozmix cement with 6% added gel. Maximum pressure was 300 psi and shut in 50 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1985

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

RECEIVED
Iona M. Leatherman
STATE CORPORATION COMMISSION Notary Public

My Commission expires:

NOV 15 1985
11-15-85

Form CP-4

CONSERVATION DIVISION