


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 26 Twp. 25 Rge. 17NE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
G of SE SE
Lease Owner Pickerell Drilling Co.
Lease Name Fatzner B#1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5/25/79 _____ 19____
Plugging completed 6/2/79 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4548
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	265	none
				4 1/2"	XXXX	3013'
					4546	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Blew well down, killed well with 30 bbls. salt water, pulled 4 1/2 x 2" swedge and installed 4 1/2" plug container. Squeezed 4 1/2" casing with 35 sacks common cement. Plug stopped at 2715', started moving slow. Kept pumping, plug 3355', casing pressured to 3200'. Checked hole and found plug at 2725', pushed plug with bailer to 4230', checked hole and shot pipe at 3805', 3685', 3550', 3420', 3300', 3010', pulled 71 joints. Squeezed hole with 5 sacks hulls, 25 sacks gel, released plug and displaced with 125 sacks 50-50 pozmix, 2% gel and 3% cc.
PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

6-11-79
CONSERVATION DIVISION
Wichita, Kansas, ss.

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 79

My commission expires _____



Margaret Melcher
Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
205 LITWIN BLDG.
WICHITA, KS. 67202
LOCATION: FATZER "B" #1
A SE SE Sec. 26-25-17W
Edwards Co., Kansas
CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

Rotary Drilling Commenced 3-07-78
Rotary Drilling Completed 3-16-78

CASING RECORD:

Surf. casing 8 5/8" set at 265' with 225sx.
Prod. casing 4 1/2" set at 4546' with 150sx.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Sand	160
Shale	267
Shale	345
Shale & Sand	1129
Blaine	1140
Shale	1220
Shale & Lime	1840
Shale & Lime	2119
Lime & Shale	2280
Lime & Shale	2495
Lime & Shale	2705
Lime & Shale	2882
Lime & Shale	3108
Shale & Lime	3295
Shale & Lime	3440
Lime & Shale	3671
Lime & Shale	3830
Lime & Shale	3984
Lime & Shale	4100
Lime	4210
Lime & Shale	4347
Lime & Shale	4457
Shale - Chert	4478
Lime	4498
Lime & Sand - RTD	4550

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1978

CONSERVATION DIVISION
Wichita, Kansas

C. W. Sebitts

The undersigned, _____, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
Attorney-in-Fact

C. W. Sebitts

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 3 day of August, 19 78, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: _____



[Signature]
Notary Public
Jo Ann Sarver