

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 27 TWP. 25 RGE. 17 E/W
Location as in quarters or footage from lines:
NE SW NW

Locate Well
correctly on above
Section Platt.

Lease Owner G L E Corporation
Lease Name Huckstep Well No. 1
Office Address 723 South High Pratt, Kansas 67124
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 6-20-63
Application for plugging filed August 1, 1983
Plugging commenced Aug. 24, 1983
Plugging completed Aug. 24, 1983
Reason for abandonment of well or producing formation

Not economical to produce
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Robert Tarbutton
Producing formation Cherokee Depth to top bottom T.D. 4640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		<u>4 1/2</u>		<u>4'</u>		<u>827.48</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

On August 12, 1983, at 10:00AM pump truck and bulk truck on location, set up pump truck put on 4" hook up. Started pumping down 4' casing and load hole, take injection rate mix 50 sks, 10/40 poz mix, release plug and wire line, start displacing plug down 3600', shut in. August 25, 1983: Started mixing 2 sx. hulls, 15 sx. gel, 70 sx cement, 10 sx. gel, 1 sx. hulls, release LA-10 top plug, started mixing last 100 sx. cement, finish mixing, wash out lines and pump, 1/2 hbl. of water to clear sledge and braden head. No vacuum when finished, but very little pressure. Job complete.


AUGUST 31-1983 TOP OF CEMENT DOWN TO 120 FT. FILL SURFACE CASING TO TOP WITH READY-MIX. SEE TICKET # 091397.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Judy Berry
Box 847 Pratt, Kansas 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of Sept, 1983

Charlene M. Dudgey
Notary Public
STATE CORPORATION COMMISSION

My Commission expires: 9/10/86

SEP 19 1983
9-19-83
CONSERVATION DIVISION
Wichita, Kansas