


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 27 Twp. 25S Rge. 17W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
C NW NW

Lease Owner Wheatland Oil & Gas
Lease Name Huckstep Well No. 1
Office Address 510 Petroleum Bldg., Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed October 9 1979
Application for plugging filed October 9 1979
Application for plugging approved October 9 1979
Plugging commenced October 9 1979
Plugging completed October 9 1979
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt, Hays, KS
Producing formation Depth to top Bottom Total Depth of Well 4512
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged as follows:

Filled hole w/mud, pumped 40 sx 50/50 pozmix, 6% gel, thru open end D.P. @ 540'; mud to 360'; pumped 40 sx thru D.P.; mud to 40'; 1/2 sx hulls & wood plug for solid bridge, pumped 10 sx to base of cellar; 5 sx in rathole. Completed @ 2 p.m. 10-9-79 by Allied

Witness: Marion Schmidt, St. Plugger, Hays, Kansas
Gary Bagby, Sterling, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Husky Drilling Co., Inc.

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1979
10-12-79
CONSERVATION DIVISION

STATE OF KANSAS COUNTY OF SEDGWICK
Jon T. Williams, Jr. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

800 Bitting Bldg., Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 1979

Geraldine Stewart
Geraldine Stewart Notary Public.

My commission expires January 12, 1981





800 Bitting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

October 9, 1979

WELL LOG- - - - - Huckstep No. 1
Located: C NW NW of Sec. 27-25S-17W, Edwards
County, Kansas.

OWNER: Wheatland Oil & Gas
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: October 3, 1979
COMPLETED: October 9, 1979

Rotary Total Depth: 4512 feet

LOG

0 - 178 Sand, gravel, clay
178 - 371 Shale
371 - 1141 Shale & Red Bed
1141 - 1160 Anhydrite
1160 - 2154 Shale & shells
2154 - 4408 Shale & lime
4408 - 4465 Lime

CASING RECORD

Ran 9 jts., 8-5/8", 28#, 8V, Rge 3, used
csg., tallied 361.49', set @ 368' KB,
w/300 sx common, 2% gel, 3% cc -
circulated - plug down @ 9:45 a.m.
by Allied.

Plugged & Abandoned @ 2 p.m. 10-9-79

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1979

CONSERVATION DIVISION
Wichita, Kansas