

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-21018-0000

Ne SW SE, Sec. 28, T 25 S, R 18 W/X

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Lease Name Newsom Well # 1

Operator: Mustang Drilling, Inc.  
Name & P. O. Box 1425  
Address Great Bend, KS 67530

County Edwards

Well Total Depth 4710 feet 153.07  
Production

~~XXXXXXXX~~ Pipe: Size 4 1/2 feet 4702

Surface Casing: Size 8 5/8 feet 469

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 12 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO D. B. Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 1st plug sand bottom back to 4580' and dump 4 sx cement on sand through

bailer. 2nd plug pump through head in sequence 3 sx hulls 10 sx gel 50 sx cement and  
10 sx gel and 1 sx hulls and released 8 5/8 rubber plug and pumped another 125 sx  
cement.

Signed Steve A. Purmont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:50 pm Day: 12 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug sand bottom back to 4580' and dump 4 sx cement on  
sand through bailer. 2nd plug pump through head in sequence 3 sx hulls 10 sx gel  
50 sx cement and 10 sx gel and 1 sx hulls and released 8 5/8 rubber plug and pumped  
another 125 sx cement.

Remarks: They recovered 2600' of 4 1/2" production casing. Sun Cementing accomplished  
plugging with 50/50 Poz with 2% gel, 3% cc. Maximum pressure 200# and shut in  
pressure at 200#.

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

INVOICED  
DATE 1-26-84  
INV. NO. 9269-W

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 23 1984  
1-23-84  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Steve A. Purmont  
(TECHNICIAN)