

7-14-88 15-047-20606-00-00

To: 1 061119
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 1/10/80

NE SE NW, SEC. 33, T 25 S, R 17 W/R
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5019

Lease Name J.D. Carroll Well # 1 "North"

Operator: Natural Gas Exploration Inc.
Name & Address P.O. Box 12108
Wichita, KS 67277

County Edwards 152.59
Well Total Depth 4695 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 396

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 14 Month: 7 Year: 19 88

Plugging proposal received from Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4675' PBTD 4470' Perfs at 4192-96, 4140-44', 4032-36' Elevation 2123'GL

1st plug bottom squeezed off with 200 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 14 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug bottom squeezed off with 200 sx cement,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1988

7-19-88
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

Signed Paul A. Luthers (TECHNICIAN)

DATE 7-26-88

INV. NO. 21668