

1060831

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,690-00-00
C SE SE, SEC. 31, T 25 S, R 17 W/E
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8778

Lease Name Mathes Well # 1

Operator: Name & Address: Midwestern Supply, Inc. bought from
Oil Property Management, Inc.
300 Patton Road
Great Bend, KS 67530

County: Edwards 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 11 Month: March Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4599' PBD 4583' Perfs at 4549-55'

1st plug pump 2 sx hulls and 50 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 11 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 50 sx cement to bottom, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 300 psi

Remarks: Recovered 2400' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 20 1986

INV. NO. 13029

3-20-86
MAR 20 1986

Signed Paul A. Luthi
(TECHNICIAN)

3-11 APR 10 1986
CONSERVATION DIVISION
Wichita, Kansas