

To: 1 060216  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-30

API NUMBER 15-047-21,396-0000  
W/2 SW NE, SEC. 19, T 25 S, R 20  
3300 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31142  
Operator: Petroleum Property Services, Inc.  
Name & Address: 155 N. Market, Ste. 1010  
Wichita, KS 67202

Lease Name Rabe Well # 1  
County Edwards  
Well Total Depth 4800 156.00 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 751

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A   
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422  
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 4 a.m. Day: 30 Month: 1 Year: 19 94

Plugging proposal received from Tony Martin  
(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1410-19'  
1st plug at 1450' with 50 sx cement, 2nd plug at 800' with 50 sx cement,  
3rd plug at 500' with 30 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None   
Operations Completed: Hour: 6 a.m. Day: 30 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement,  
2nd plug at 800' with 50 sx cement,  
3rd plug at 500' with 30 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB - 2 1994  
2-2-94  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED  
FEB 04 1994

DATE: ~~XXXX~~ did not observe this plugging.

INV. NO. 39855  
1-30

Signed Case Morris (TECHNICIAN)