

To: 1 070014
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

8-16

API NUMBER 15- 047-21,428-0000
App. SW SW SW, SEC. 19, T 25 S, R 20 W/X
400 feet from S section line
330 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422
Operator: Abercrombie Drilling, Inc.
Name & Address: 150 N. Main, Ste. 801
Wichita, KS 67202-1383

Lease Name Herrmann "D" Well # 1
County Edwards 156.00
Well Total Depth 4800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling, Inc. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 16 Month: 8 Year: 19 97

Plugging proposal received from Rich Wheeler
(company name) Duke Drilling, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1405-23'

1st plug at 1450' with 50 sx cement, 2nd plug at 370' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Scott Alberg
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6 p.m. Day: 16 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement,

2nd plug at 370' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 19 1997
8-19-97

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED (If additional description is necessary, use BACX of this form.)

I (XXX / did not) observe this plugging.

DATE: 8-20-97

Signed _____ (TECHNICIAN)

INV. NO. 48822