

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21135-00-01
Spot: SWSW Sec/Twnshp/Rge: 4-24S-10W
660 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: HURST OWWO Well Number: 1
County: RENO Total Vertical Depth: 3850 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 914 E DOUGLAS
WICHITA, KS 67202

Conductor Pipe: Size feet: 9/25.13
Surface Casing: Size 8.625 feet: 297 160 SX CMT
Production: Size 4.5 feet: 3725 285 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/13/2003 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TIM HELLMAN Company: Phone: (316) 734-8380

Proposed Plugging Method: ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS.

RECEIVED
KANSAS CORPORATION COMMISSION
1-23-03
JAN 23 2003

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI
Date/Time Plugging Completed: 01/13/2003 2:00 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 2692' & 4 sx of common, shot 4 1/2 casing, off at 2010', pulled to 1450', pumped 35 sx, pulled to 950', pumped 35 sx, pulled to 300', circulate cement to surface.

Remarks: ALLIED #4353 60/40 4%

Plugged through: CSG

District: 02

Signed

Jack Luthi
(TECHNICIAN)

INVOICED

DATE 1-24-03
INV. NO. 2003061108