

11-28 RECEIVED  
KANSAS CORPORATION COMMISSION

2-040746 187R

DEC 01 1992  
12-1-92  
CONSERVATION DIVISION  
WICHITA, KS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-155-21,332 - 0000

SE SE NE, SECTION 35 TOWNSHIP 24 RANGE 9W

OPERATOR LICENSE # 9354 2970 FEET FROM S SECTION LINE  
330 FEET FROM E SECTION LINE

OPERATOR Central Energy Corp.  
NAME & P. O. Box 47590  
ADDRESS Wichita, KS 67201

LEASE NAME: Cole #1 128.18  
COUNTY: Reno  
WELL TOTAL DEPTH: 3944'

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 213'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: White & Ellis  
ADDRESS: Great Bend LICENSE: 5420

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Judy

COMPANY NAME: White & Ellis PHONE: \_\_\_\_\_  
WERE: 35 sx 1375' - 35 sx 900' - 35 sx 265' - 25 sx 60'  
- 15 sx RH - 10 sx MH

PLUGGING PROPOSAL RECEIVED BY: Mike Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( \_\_\_\_\_ ) NONE ( X )

COMPLETED: HOUR: 1615 DAY: 28 MONTH: 11 YEAR: 1992

ACTUAL PLUGGING REPORT:

Drl pipe run open-end to 1375' & 35 sx cmt spotted -  
drl pipe pulled to 900' & 265' where 35 sx cmt spotted  
at each depth - drl pipe pulled to 60' & 25 sx cmt circ  
to surf - rat hole circ 15 sx cmt - mouse hole w/10 sx

REMARKS: Allied #5927 60/40 4% gel

I DID NOT OBSERVE THIS PLUGGING.

DATE DEC 10 1992

INV. NO. 37067  
11-28-92

/s/  
Steve Van Gieson (AGENT)

JAN 22 1993